

FINAL REPORT APPENDIX

VOLUME

Alameda Corridor East Phase II Grade Separation Traffic Study and Concept Plans December 2011

3



Prepared by:



KOA CORPORATION
PLANNING & ENGINEERING

1100 Corporate Center Drive, Suite 201
Monterey Park, California 91754
Telephone: (323) 260-4703
Fax: (323) 260-4705

Prepared for:

Alameda Corridor-East Construction Authority
4900 Rivergrade Road, Suite A120
Irwindale, CA 91760
Telephone: (626) 962-9292
Fax: (626) 962-9393

Appendices – Volume 3

APPENDIX G - LEMON AVENUE AT UPRR LOS ANGELES SUBDIVISION

APPENDIX H - FAIRWAY DRIVE AT UPRR LOS ANGELES SUBDIVISION

APPENDIX I - ROSE HILLS ROAD AT UPRR LOS ANGELES SUBDIVISION

APPENDIX J - TURNBULL CANYON ROAD AT UPRR LOS ANGELES SUBDIVISION

APPENDIX K - DURFEE AVENUE AT UPRR LOS ANGELES SUBDIVISION

APPENDIX L - FULLERTON ROAD AT UPRR LOS ANGELES SUBDIVISION

APPENDIX M - PUENTE AVENUE AT UPRR ALHAMBRA SUBDIVISION


APPENDIX N - FAIRWAY DRIVE AND LEMON AVENUE AT UPRR ALHAMBRA SUBDIVISION OPTIONS

APPENDIX O - HAMILTON BOULEVARD AT LOS ANGELES/ALHAMBRA SUBDIVISION


APPENDIX P - SAN ANTONIO AVENUE AT LOS ANGELES/ALHAMBRA SUBDIVISION

APPENDIX Q - MONTEBELLO OPTIONS

APPENDIX G
LEMON AVENUE AT UPRR LOS ANGELES SUBDIVISION



Source: JL Patterson & Associates, Inc.




Source: J.L. Patterson & Associates, Inc.



Source: J.L. Patterson & Associates, Inc.



Source: J.L. Patterson & Associates, Inc.



Source: J.L. Patterson & Associates, Inc.



ACE Phase II Grade Separation Traffic Study and Concept Plans

Appendix G - Page 7 of 7

LEMON AVENUE (LOS ANGELES SUBDIVISION) DETOUR CONCEPT PLAN - UNDERPASS ALTERNATIVE

ACE Task 2 Preliminary Cost Estimate


Lemon Avenue - LA Sub
Underpass

WORK DESCRIPTION-LEMON AVENUE UNDERCROSSING	EST. QTY	UNIT	UNIT PRICE	TOTAL PRICE
CIVIL CONTRACTOR				
Civil / Grading/Drainage				
Mobilization/Demobilization (8% Civil)	1	LS	\$1,636,970	\$ 1,636,970
Clearing & Grubbing (3% Civil)	1	LS	\$613,864	\$ 613,864
Traffic (7% Civil)	1	LS	\$1,432,349	\$ 1,432,349
Earth Work - Cut	10,000	CY	\$40	\$ 400,000
Earth Work -Fill		CY	\$30	\$ -
Civil Work (C&G, AC, SW, Etc.)	1	LS	\$1,904,870	\$ 1,904,870
Detour Road	1	LS	\$500,000	\$ 500,000
Environmental	1	LS	\$300,000	\$ 300,000
Crossings				
Remove Existing Panels (3 Pairs)	360	LF	\$20	\$ 7,200
New Crossing Panels (2 Pairs)	240	LF	\$1,200	\$ 288,000
Roadway Total =		\$	7,083,253	
Structural				
Bridge inclusive of abutment and related items, Soldier pile lagging walls for roadways, and structural excavation. Not inclusive of pump station	1	LS	\$15,192,060	\$ 15,192,060
Utilities Note 1 & 2				
Water, Electrical, Gas, Storm Drain, Sewer & Fiber Optic	1	LS	\$1,870,000	\$ 1,870,000
CIVIL CONTRACTOR TOTAL				\$ 24,145,000
UNION PACIFIC RAILROAD				
Track work				
Remove & Relocate Turnout	4	EA	\$175,000	\$ 700,000
Install New Track	3,540	TF	\$350	\$ 1,239,000
Remove Track	3,540	TF	\$120	\$ 424,800
Shift Track	2,400	TF	\$225	\$ 540,000
Crossings				
Remove Crossing House and Gates	1	LS	\$50,000	\$ 50,000
New Temporary Crossing House and Gates Removal and Reprogramming of Temporary Crossings Detour Road	3	EA	\$500,000	\$ 1,500,000
UPPR RAILROAD TOTAL				\$ 4,453,800
SUB TOTAL				\$ 28,599,000
PROJECT COST				
CIVIL / STRUCTURAL ENGINEERING:				
Geotechnical Investigation (3% Construction)	1	LS	\$857,970	\$ 857,970
Survey/ Aerial Mapping (2% Construction)	1	LS	\$571,980	\$ 571,980
Design & Design Support (10% Construction)	1	LS	\$2,859,900	\$ 2,859,900
Right-of-Way-Acquisitions Note 3, 4 & 5	1	LS	\$23,436,126	\$ 23,436,126
Construction Management (10% Construction)	1	LS	\$2,859,900	\$ 2,859,900
Agency Costs (16% Construction) Note 6	1	LS	\$4,575,840	\$ 4,575,840
Program Management Costs (8% Construction) Note 7	1	LS	\$2,287,920	\$ 2,287,920
Flagging (6% Construction)	1	LS	\$1,715,940	\$ 1,715,940
Permitting/City Requirement (1% Construction)	1	LS	\$285,990	\$ 285,990
Sub Total PROJECT COST				\$ 39,452,000
Project Costs not Inclusive of ROW Acquisitions		\$	16,015,440.00	
Not Inclusive of ROW Acquisitions				
Contingency				
Total				\$ 68,051,000
30%				\$ 13,384,462
Grand Total				\$ 81,435,000

Notes

- Utility relocation cost estimates assume all affected utilities (sewer and storm drain) can be relocated by gravity flow systems similar to the existing systems.
- Cost for drainage item includes construction of one storm drain pump station at the project area.
- Right of Way cost estimates are based on \$100/SF which covers the land and building allowance for full takes or areas affected by part takes.
- Right of Way costs do not include any associated relocation costs or severance damages to the business operators.
- Right of Way costs include a 26% allowance for acquisition costs. (appraisals, negotiation, labor, legal, closing cost, etc.)
- Agency Costs include Agency Project Management direct labor and Agency indirect costs.
- Program Management costs include third party project support costs such as community outreach, environmental management, DBE and labor compliance, and property survey.
- This estimate is prepared using construction cost information based on current dollar cost as of 2011.

APPENDIX H
FAIRWAY DRIVE AT UPRR LOS ANGELES SUBDIVISION




Source: J.L. Patterson & Associates, Inc.




ACE Phase II Grade Separation Traffic Study and Concept Plans

FAIRWAY DRIVE (LOS ANGELES SUBDIVISION) ROADWAY CONCEPT PLAN - UNDERPASS ALTERNATIVE


Appendix H - Page 1 of 7



Source: JL Patterson & Associates, Inc.




Source: J.L. Patterson & Associates, Inc.



Source: J.L. Patterson & Associates, Inc.




ACE Phase II Grade Separation Traffic Study and Concept Plans




Source: J.L. Patterson & Associates, Inc.



ACE Phase II Grade Separation Traffic Study and Concept Plans





Source: J.L. Patterson & Associates, Inc.



ACE Phase II Grade Separation Traffic Study and Concept Plans

FAIRWAY DRIVE (LOS ANGELES SUBDIVISION) ROADWAY DETOUR CONCEPT PLAN - UNDERPASS ALTERNATIVE

Appendix H - Page 7 of 7

ACE Task 2 Preliminary Cost Estimate


Fairway Drive - LA Sub
Underpass

WORK DESCRIPTION-FAIRWAY DRIVE UNDERCROSSING	EST. QTY	UNIT	UNIT PRICE	TOTAL PRICE
CIVIL CONTRACTOR				
Civil / Grading/Drainage				
Mobilization/Demobilization (8% Civil)	1	LS	\$1,966,214	\$ 1,966,214
Clearing & Grubbing (3% Civil)	1	LS	\$737,330	\$ 737,330
Traffic (7% Civil)	1	LS	\$1,720,437	\$ 1,720,437
Earth Work - Cut	130,600	CY	\$40	\$ 5,224,000
Earth Work -Fill		CY	\$30	\$ -
Civil Work (C&G, AC, SW, Etc.)	1	LS	\$1,622,862	\$ 1,622,862
Detour Road	1	LS	\$500,000	\$ 500,000
Environmental	1	LS	\$300,000	\$ 300,000
Crossings				
Remove Existing Panels (3 Pairs)	360	LF	\$20	\$ 7,200
New Crossing Panels (2 Pairs)	240	LF	\$1,200	\$ 288,000
Roadway Total =	12,366,043			
Structural				
Bridge inclusive of abutment and related items, Soldier pile lagging walls for roadways, and structural excavation. Not inclusive of pump station	1	LS	\$14,455,610	\$ 14,455,610
Utilities Note 1 & 2				
Water, Electrical, Gas, Storm Drain, Sewer & Fiber Optic	1	LS	\$2,180,000	\$ 2,180,000
CIVIL CONTRACTOR TOTAL				\$ 29,001,653
UNION PACIFIC RAILROAD				
Track work				
Remove & Relocate #7 Turnout	2	EA	\$175,000	\$ 350,000
Install New Track	2,898	TF	\$350	\$ 1,014,300
Remove Track	2,898	TF	\$120	\$ 347,760
Shift Track	4,366	TF	\$225	\$ 982,350
Crossings				
Remove Crossing House and Gates	1	LS	\$50,000	\$ 50,000
New Temporary Crossing House and Gates Removal and Reprogramming of Temporary Crossings Detour Road	3	EA	\$500,000	\$ 1,500,000
UPPR RAILROAD TOTAL				\$ 4,244,410
SUB TOTAL				\$ 33,246,000
PROJECT COST				
CIVIL / STRUCTURAL ENGINEERING:				
Geotechnical Investigation (3% Construction)	1	LS	\$997,380	\$ 997,380
Survey/ Aerial Mapping (2% Construction)	1	LS	\$664,920	\$ 664,920
Design & Design Support (10% Construction)	1	LS	\$3,324,600	\$ 3,324,600
Right-of-Way-Acquisitions Note 3, 4 & 5	1	LS	\$32,656,932	\$ 32,656,932
Construction Management (10% Construction)	1	LS	\$3,324,600	\$ 3,324,600
Agency Costs (16% Construction) Note 6	1	LS	\$5,319,360	\$ 5,319,360
Program Management Costs (8% Construction) Note 7	1	LS	\$2,659,680	\$ 2,659,680
Flagging (6% Construction)	1	LS	\$1,994,760	\$ 1,994,760
Permitting/City Requirement (1% Construction)	1	LS	\$332,460	\$ 332,460
Sub Total PROJECT COST				\$ 51,275,000
Project Costs not Inclusive of ROW Acquisitions				\$ 18,617,760
Not Inclusive of ROW Acquisitions				
			Total	\$ 84,521,000
			Contingency	\$ 15,559,220
Grand Total				\$ 100,080,000


Notes

- Utility relocation cost estimates assume all affected utilities (sewer and storm drain) can be relocated by gravity flow systems similar to the existing systems.
- Cost for drainage item includes construction of one storm drain pump station at the project area.
- Right of Way cost estimates are based on \$100/SF which covers the land and building allowance for full takes or areas affected by part takes.
- Right of Way costs do not include any associated relocation costs or severance damages to the business operators.
- Right of Way costs include a 26% allowance for acquisition costs. (appraisals, negotiation, labor, legal, closing cost, etc.)
- Agency Costs include Agency Project Management direct labor and Agency indirect costs.
- Program Management costs include third party project support costs such as community outreach, environmental management, DBE and labor compliance, and property survey.
- This estimate is prepared using construction cost information using current dollar cost as of 2011.




APPENDIX I
ROSE HILLS ROAD AT UPRR LOS ANGELES SUBDIVISION



Source: J.L. Patterson & Associates, Inc.



Source: JL Patterson & Associates, Inc.



Source: J.L. Patterson & Associates, Inc.

